



SALUS FIRE LTD



Salus Fire Ltd
3 The Spinney
Silsoe
Bedfordshire
MK45 4GS
Tel: 0330 311 2512

Date: 19/5/2026

Job reference: SAL568

For the attention of: Darren LES Limited

RE: Liscombe Park

Site Address:

Specification:

Drawings:

System standby time:

Category:

Darren,

Price includes supply, second fix, testing and commissioning of the AOV system. All cabling to be carried out by others. Quotation is based on existing actuators and AOV window being fully operational at the time of commissioning. In the event of any faults or non operation of existing actuator, or AOV window, further investigation and any remedial works will be subject to additional costs.

Equipment schedule

EV-301 Smoke Ventilation AOV Control Panel with Battery Back-up	1
Firemans Override Switch EV-HE077 Sustainable BIOBased Housing	1
Photoelectric Smoke Detector	2
Engineer	1
Commission	1

Total: £1,244.60

VAT

Our quotation is exclusive of VAT, which will be charged at the rate ruling on the date of despatch.

Works

- All works are carried out in accordance with BS5839-1:2025 and will be carried out in normal working hours.
- All 2nd fix equipment will be supplied, installed and commissioned by Salus fire Ltd.
- Quote is based on one continuous visit to 2nd fix and commission, any unacceptable delays or downtime not caused by Salus fire Ltd will be chargeable.
- Quote is based on the use of steps, any further access equipment required will need additional costing.

Exclusions

- Builders works.
- Any voids found to be over 800mm may require additional detection and as such are not covered by this quote.
- Installation of 230v supply.

Loop Capacity

We have assumed for the purpose of our quotation that there is adequate spare capacity on the existing Fire Alarm System for the addition of the additional devices. Should this be found not to be the case, then we will advise accordingly and a follow up quotation will be submitted.

Interface Devices

Where Interface Devices are included in our quotation, for the purpose of operating various plant and equipment, in the event of a fire alarm system activation, then the following applies, unless otherwise stated in our offer. The cabling between the contacts of our Interface Device and the plant/equipment control system circuit, together with the final connections are not included in this quotation, and is the responsibility of the client or his contractor. It is also the responsibility of the client or his contractor, to ensure that the electrical rating of the equipment being switched, does not exceed the contact rating of the Interface Device.

Commissioning

On completion of the installation our engineers will carry out complete commissioning and testing of the system. The alarm sounder positions have been selected in line with our experience in the installation of alarm systems, and are designed to give a sound level as required under the appropriate requirement of BS5839-1:2025. The design is given in good faith, but due to the complexity of sound level variation caused by wall partitions, carpeting, furniture and doors, we cannot guarantee that all areas will have the correct audibility level.

We would be pleased to conduct an audibility test after installation, and recommend any further sounders that may be required, subject to your instructions.

Validity

This quotation is valid for a period of 60 days from the tender date for orders placed within that time and for delivery within the stated delivery period.

Terms and Conditions

Salus fire Ltd standard Terms & Conditions apply as standard. By accepting this quotation, you are agreeing to our terms and conditions which can be supplied on demand. Payment is due 30 days from date of invoice or application. Equipment and materials will be invoiced as and when delivered to site.

Warranty

All equipment carries a 12-month warranty covering manufacturing defects and poor workmanship.



SALUS FIRE LTD



Salus Fire Ltd
3 The Spinney
Silsoe
Bedfordshire
MK45 4GS
Tel: 0330 311 2512

Delivery

Standard equipment is generally supplied from stock, but it is advisable to allow 2 weeks wherever possible in case of temporary stock shortages.

Thank you for the opportunity to offer our quotation for this project. We hope that we have interpreted your requirements correctly and that our recommendations are of assistance. Please read our proposal carefully and advise us if you feel that we may have misunderstood your enquiry in any way or failed to include any relevant requirements.

We look forward to receiving your further instructions, but should you require any further assistance in the meantime, please do not hesitate to ask.

Yours sincerely

Joe Abella

Telephone: 0330 311 2512

Mobile: 07917808951

Email: Joe@salusfire.com

Website: www.salusfire.com